KADUR FOREST DIVISION.

Abstract Notification dated 25th May 1937.

The attention of the public is invited to the detailed notification, calling for tenders for the collection and carting of rough sandlwood from Yemmedoddi Estate to Kadur Railway Station during the year 1937-38, published on page 854, Part VI of the *Mysore Gazette*, dated 3rd June 1937.

M. A. MUTHANNA,
District Forest Officer.

CHITALDRUG DISTRICT.

Abstract Notification dated 26th May 1937.

The attention of the public is invited to the detailed notification of date, published on page 855, Part VI of the *Mysore Gazette*, dated 3rd June 1937, regarding the resale of the right to cut and remove grass crop of Nerlagundi Plantation of Chitaldrug Range, up to end of June 1938, the date of sale being 18th June 1937.

A. V. KESAVIENGAR,
District Forest Officer.

ENGINEERING DEPARTMENT.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notice dated 21st—25th May 1937.

The attention of the public is invited to the notification, calling for re-tenders for the work of "Constructing drains in Tumkur Town," published in pages 840-841, Part VI of the *Mysore Gazette*, dated 27th May 1937.

The last date for receiving tenders is 21st June 1937.

N. KRISHNIENGAR,
Sanitary Engineer.

BUILDINGS DIVISION, BANGALORE.

Abstract Notification dated 28th May 1937.

The attention of the public is hereby invited to the detailed notification, calling for tenders for tarring the road with Bitumen emulsion, side roads of Sir K. Seshadri Iyer's Memorial Hall in Cubbon Park, Bangalore, published in pages 858-859, Part VI of the *Mysore Gazette*, dated 3rd June 1937.

The last date for the receipt of the tender is 18th June 1937.

Abstract Notification dated 29th May 1937.

The attention of the public is hereby invited to the detailed notification, calling for tenders for tarring the road with Bitumen emulsion from Sri Krishnarajendra Road to rear of Sir K. Seshadri Iyer's Memorial Hall, Bangalore, published on pages 859-860, Part VI of the *Mysore Gazette*, dated 3rd June 1937.

The last date for the receipt of the tender is 18th June 1937.

Abstract Notification dated 29th May 1937.

The attention of the public is invited to the notification dated 29th May 1937, published on pages 860-861, Part VI of the *Mysore Gazette*, dated 3rd June 1937, calling for tenders for providing and fixing iron works required for the construction of a weaving shed attached to the Sri Krishnarajendra Technological Institute at Bangalore.

The last date for the receipt of the tenders is 14th June 1937.

Abstract Notification dated 29th May 1937.

The attention of the public is hereby invited to the detailed notification calling for tenders for extending on the south the Record Block in the District Office for providing extra accommodation required for keeping Judicial records of the Deputy Commissioner's Office, Bangalore, published in pages 862-863, part VI of the *Mysore Gazette*, dated 3rd June 1937.

The last date for the receipt of the tender is 18th June 1937.

Abstract Notification dated 29th May 1937.

The attention of the public is hereby invited to the detailed notification calling for tenders for extending the Record Block in the District and Sessions Judge's Court on the right side of the Central Record Rooms in the District Office compound, Bangalore, published in pages 863-864, Part VI of the *Mysore Gazette*, dated 3rd June 1937.

The lsat date for the receipt of the tender is 25th June 1937.

Abstract Notification dated 29th May 1937.

The attention of the public is hereby invited to the detailed notification calling for tenders for constructing a Restaurant for the District Office, Bangalore, published in pages 865-866, Part VI of the *Mysore Gazette*, dated 3rd June 1937.

The last date for the receipt of the tender is 18th June 1937.

B. R. GARUDACHAR,
Executive Engineer.

KOLAR DIVISION.

Notification dated 31st May 1937.

1. Sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 12 NOON on 28th June 1937 for restoring Linganahalli Dinnekere minor tank . R. No. 514 of Malur Taluk.

2. Tenders in the prescribed form obtainable from the office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for Restoring Linganahalli Dinnekere." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 270 (Rupees two hundred and seventy only) in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money of the successfu tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash, will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 28th May 1937 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the Departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's office, Kolar, on all working days, between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department Schedule of Rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of February 1938 failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day, which will ordinarlly be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transation.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.

(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.

(3) Provide mortar mills, and sheds, to keep materials under cover and also for workmen

(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves parahs, shoring, strutting and other requisite protective appliances during the progress of the work.

(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including the necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and giv such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Abstract estimate for restoring Linganahalli Dinnekere, Minor Tank, Reg. No. 514 of Malur Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund R. L. 55·00 Top width 4½ feet slopes 1½ : 1 and 2 : 1.				
1			Rs. a. p.		
2	Earthwork to bund including watering and consolidation	C.yds.	0 3 0	6083	
3	Turfing the slopes	S.yds.	0 0 9	3936	
	Removing and Resetting and Stone Revetment with new jelly backing and wedging	C.yds.	0 8 0	165	
4	New stone revetment	C.yds.	1 8 0	1126	
5	Providing and fixing Grade stones including cutting figures, painting, etc., complete ..	Each.	1 8 0	15	
6	Do Index stones	Each.	0 6 0	15	
7	Do B. M. stones	Each.	2 8 0	2	
8	Do Reg. No. and Date stones ..	Each.	3 0 0	1	
9	Do Gauge Stone	Each.	15 0 0	1	
10	Jungle clearing	Lump	sum rupees		
11	Puddle wall	C.yds.	0 9 0	125	
	Total Rupees for Bund	..	..	..	
	II. Constructing a masonry sluice at R. L. 44.00.				
1	Earthwork excavating foundation	C.yds.	0 3 0	39	
2	Do Filling in consolidation ..	C.yds.	0 3 0	43	
3	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	245	
4	Burnt brick in surki mortar	C.ft.	0 4 6	265	
5	Burnt stone slabs 6" thick	S.ft.	0 5 0	210	
6	Surki plastering	S.yds.	4 0 0	3.84	
7	Providing plug and rod with locking arrangements.	Lump	sum rupees		
8	Drilling holes and Cutting grooves	Lump	sum rupees		
	Total for Sluice Rupees ..	..	..	..	
	III. Constructing a masonry waste weir 96 feet long at R. L. 50.00.				
1	Earthwork excavating foundation	C.yds.	0 3 0	426	
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	821	
3	Burnt Brick in surki-mortar	C.ft.	0 4 6	1821	
4	Burnt stone slabs 6" thick and dressed ..	S.ft.	0 5 0	582	
5	Surki mortar plastering	Sqr.	4 0 0	24.35	
6	New stone work for apron	C.yds.	1 8 0	303	
	Total for Weir Rs. ..	..	..	..	

P. RAJAGOPALAN,
Executive Engineer.

TUMKUR DIVISION.

Notification dated 31st May 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P. M. on 26th June 1937, for restoring breached katte across the weir halla of Bugudanahalli Tank, Tumkur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 600 (six hundred only) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Restoring breached katte across the weir halla of Bugudanahalli, Tumkur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract Estimate for restoring the breached katte across the weir halla of Bugudanahalli Amanikere in Tumkur Taluk.

No.	Items of work	Per	Quantity	Rate
	Halla Portion.			
1	Removing silt in bed	C.yd.	1180	0 3 0
2	Earthwork excavation and using the stuff for rear portion of bund, etc., complete	C.yd.	86	0 4 0
3	Puddle wall	C.yd.	50	0 12 0
4	Gravel backing to revetment with lead consolidation	C.yd.	132	0 12 0
5	Rough stone pitching lead of 3 to 4 miles	C.yd.	198	2 4 0
6	Earthwork embankment with selected soil	C.yd.	2,068	0 8 0
7	Earthwork to ring bund with watering and tamping	C.yd.	482	0 5 0
	Bund.			
1	Earthwork removing top soil and using the same for rear slope of bund with watering and tamping	C.yd.	1,752	0 3 6
2	Excavating trench and using the stuff for slope of bund	C.yd.	492	0 3 6
3	Gravel backing with lead to revetment with consolidation	C.yd.	23	0 12 0
4	Rough stone pitching lead of 3 to 4 miles	C.yd.	35	2 4 0
5	Earthwork embankment with watering and tamping	C.yd.	12,408	0 5 0
6	Turfing	S.yd.	9,729	0 1 0
7	Grade stones with bed slabs engraving of figures and painting, etc., complete	No.	30	2 8 0
8	Registered No. stone with date stone	No.	1	5 0 0
9	Index stones with engraving figures and painting	No.	30	0 8 0
10	Guage stone 12 feet	No.	1	15 0 0
11	B. M. Stones	No.	2	3 0 0

No.	Items of work	Per	Quantity	Rate
	Waste Weir.			
1	Concrete in surki mortar	C.ft.	2,021	0 4 0
2	Burnt stone or trap stone in surki mortar	C.ft.	4,615	0 5 0
3	Pointing with surki mortar	Sqr.	45.86	2 8 0
4	Burnt stone slabs 6" thick rough dressed and fixed ..	S.ft.	888	0 8 0
5	Jelly filling	C.yd.	40	1 0 0
6	Joggle including fixing	Each	95	1 0 0
7	New rough stone work—lead 3 to 4 miles	C.yd.	397	2 4 0
	Left sluice No. I. Cill of sluice R. L. 47.00.			
1	Earthwork excavation	C.yd.	37	0 4 0
2	Concrete in surki mortar	C.ft.	314	0 4 0
3	Burnt brick or stone in surki mortar	C.ft.	490	0 5 0
4	Burnt stone slabs 6" thick dressed with grooves, etc., and fixed	S.ft.	27	0 10 0
5	Burnt stone slabs roughly dressed 6" thick	S.ft.	305	0 8 0
6	Cement plastering	Sqr.	1.8	10 0 0
7	Rough stone work new—lead 3 to 4 miles	C.yd.	10	2 4 0
	Right sluice—Cill at R. L. 47.00.			
1	Earthwork excavation	C.yd.	54	0 4 0
2	Concrete in surki mortar	C.ft.	314	0 4 0
2	Burnt brick or stone in surki mortar	C.ft.	490	0 5 0
4	Burnt stone slabs 6" thick nicely dressed with cutting grooves and fixed	S.ft.	27	0 10 0
5	Burnt stone slabs 6" thick roughly dressed	S.ft.	305	0 8 0
6	Cement plastering	Sqr.	1.80	10 0 0
7	Rough stone work, new	C.yd.	10	2 4 0

D. KRISHNA RAO,
Executive Engineer.

HASSAN DIVISION.

Abstract Notification dated 24th May 1937.

The attention of the public is invited to the notification calling for tenders for the restoration of Hyrane Doddakere, Reg. No. 729 of Hassan Taluk, published on pages 819-820 of Part VI of the *Mysore Gazette*, dated 27th May 1937.

The last date for receiving the tenders is 16th June 1937.

Abstract Notification, dated 24th May 1937.

The attention of the public is invited to the notification calling for tenders for opening out a road from Alur to Biccodu in Hassan District, published on pages 820-822 of Part VI of the *Mysore Gazette*, dated 27th May 1937.

The last date for receiving tenders is 14th June 1937.

Abstract Notification dated 28th May. 1937.

The attention of the public is invited to the notification calling for tenders for the extension of sluice channel under Budanur Tank, Arkalgud Taluk, Hassan District, published on pages 870-871, Part VI of the *Mysore Gazette*, dated 3rd June 1937.

The last date for receiving tenders is 18th June 1937.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.